



**NO SCALE**

**NOTES:**

1. Backfill of trench from top of 67 Crushed Stone Bedding to the top of trench shall be Compacted to 95% maximum dry density in accordance with Section 911. No grits will be allowed.
2. The compaction requirement will be strictly enforced by the City.
3. The £ of the proposed storm sewer should be offset from the property line.
4. The cost of the 67 Crushed Stone Bedding, Compacted Fill and Backfill shall be included in Item 901.
5. Minimum width of trench and quantities are as shown on drawings S-1 or S-3.

PREVIOUSLY 001A5

APPROVED 5 MAY 86  
DATE

*Perry J. Payne*  
CITY ENGINEER

**TYPICAL TRENCH  
DETAIL**

**FOR STORM SEWERS  
OUTSIDE R/W WITH  
COVER 30" OR LESS**

CITY OF LANCASTER, OHIO  
DEPARTMENT OF ENGINEERING

**STANDARD  
CONSTRUCTION DRAWING**

DWG. BY: S.L.H.  
CHK'D BY: R.M.

FILE NUMBER  
S-5

REVISED: