



**NOTES:**

BACKING DESIGNED FOR 3000 PSF SOIL BEARING.

CONCRETE TO BE PLACED AGAINST UNDISTURBED EARTH.

PROVIDE CLEARANCE FOR REMOVAL OF BOLTS.

4" VALVES OR LARGER WILL BE APPROXIMATELY 2' OFF MAIN LINE.

TEES WILL BE VALVED.

ANY CHANGES IN THIS VALVE SETTING MUST BE APPROVED BY THE LANCASTER DIVISION OF WATER DEPARTMENT.

APPROVED \_\_\_\_\_  
 \_\_\_\_\_  
 CITY ENGINEER

**TYPICAL 4" OR LARGER  
 TEE AND VALVE SETTING  
 AND BACKING FOR TEES**

CITY OF LANCASTER, OHIO  
 DEPARTMENT OF ENGINEERING

STANDARD  
 CONSTRUCTION DRAWING

DWG. BY: ...MAC...  
 CHK'D BY: .....

FILE NUMBER  
**W-10**

REVISED: 8/15/13